



Asbestos Assessment

St. Charles Mountain
150 East 5th Street, Hamilton, ON,
L9A 2Z8

Prepared for:

**Hamilton-Wentworth Catholic
District School Board**

90 Mulberry Street
Hamilton, Ontario, L8N 3R9

August 31, 2023

Pinchin File: 320582.004



Asbestos Assessment

St. Charles Mountain, 150 East 5th Street, Hamilton, ON, L9A 2Z8
Hamilton-Wentworth Catholic District School Board

August 31, 2023
Pinchin File: 320582.004

Issued to: Hamilton-Wentworth Catholic District School Board
Issued on: August 31, 2023
Pinchin File: 320582.004
Issuing Office: Hamilton, ON
Primary Contact: Emily Balfour, Project Manager, ebalfour@pinchin.com

Author:

Emily Balfour
Project Manager
365.889.5147
ebalfour@pinchin.com

Reviewer:

Damian Palus, C.E.T.
Operations Manager
289.678.0694
dpalus@pinchin.com



EXECUTIVE SUMMARY

Hamilton-Wentworth Catholic District School Board (Client) retained Pinchin Ltd. (Pinchin) to conduct an asbestos building materials assessment of St. Charles Mountain located at 150 East 5th Street, Hamilton, ON, L9A 2Z8.

The objectives of the assessment were to document the locations of asbestos building materials, evaluate their condition and develop corrective action plans as required for the purposes of long-term management. The results of this assessment are not intended for construction, renovation, demolition or project tendering purposes.

SUMMARY OF RECOMMENDATIONS

The following is a summary of significant recommendations; refer to the body of the report for detailed recommendations:

1. Maintain the Asbestos Management Program (AMP)
2. Perform a re-assessment of asbestos materials on an annual basis.
3. Perform a pre-construction assessment and remove all ACM prior to alteration or maintenance work if ACM may be disturbed by the work.
4. Follow appropriate safe work procedures when handling or disturbing asbestos.
5. Sample any presumed ACM prior to alteration or maintenance work if presumed ACM may be disturbed by the work.
6. Update the asbestos inventory report upon completion of any abatement and removal of asbestos-containing materials.

This Executive Summary is subject to the same standard limitations as contained in the report and must be read in conjunction with the entire report.



TABLE OF CONTENTS

1.0 INTRODUCTION AND SCOPE 1
 1.1 Scope of Assessment 1
2.0 METHODOLOGY 1
3.0 BACKGROUND INFORMATION 1
 3.1 Building Year of Construction and Additions 1
 3.2 Existing Reports 1
 3.3 Inaccessible Locations 2
4.0 FINDINGS 2
 4.1 Excluded Asbestos Materials 2
 4.2 Summary of Building Materials 3
5.0 RECOMMENDATIONS 6
 5.1 General 6
 5.2 Remedial Work 6
 5.3 On-going Management and Maintenance 6
6.0 TERMS AND LIMITATIONS 6
7.0 REFERENCES 7

APPENDICES

APPENDIX I Drawings
APPENDIX II Asbestos Analytical Certificates
APPENDIX III Methodology
APPENDIX IV Location List
APPENDIX V Summary Report / Sample Log
APPENDIX VI HMIS All Data Report



1.0 INTRODUCTION AND SCOPE

Hamilton-Wentworth Catholic District School Board (Client) retained Pinchin Ltd. (Pinchin) to conduct an asbestos building materials assessment of St. Charles Mountain located at 150 East 5th Street, Hamilton, ON, L9A 2Z8.

Pinchin performed the assessment on July 31, 2023.

The objectives of the assessment were to document the locations of asbestos building materials, evaluate their condition and develop corrective action plans as required. This assessment is only to be used for the purposes of long-term management and routine maintenance. The results of this assessment are not to be used for construction, renovation, demolition, or project tendering purposes.

1.1 Scope of Assessment

The assessment was performed to establish the location and type of asbestos building materials incorporated in the structure(s) and its finishes. The **assessed area** consisted of all parts of the building, excluding the roof.

2.0 METHODOLOGY

Pinchin conducted a room-by-room assessment (rooms, corridors, service areas, exterior, etc.) to identify the asbestos-containing building materials as defined in the scope.

The assessment was limited to non-intrusive testing. Concealed spaces such as those above solid ceilings and within shafts and pipe chases were accessed via existing access panels only. Demolition of walls, solid ceilings, structural items, interior finishes or exterior building finishes, to determine the presence of concealed materials was not conducted.

For further details on the methodology including test methods, refer to Appendix III.

3.0 BACKGROUND INFORMATION

3.1 Building Year of Construction and Additions

| Item | Details |
|----------------------|---------|
| Year of Construction | 1972 |

3.2 Existing Reports

Pinchin previously prepared the following report, which has been reviewed as part of this assessment:

- Asbestos Reassessment Report, St. Charles Mountain, August 2022, Pinchin File No. 303992.004.



3.3 Inaccessible Locations

Inaccessible locations (rooms or areas), if any, are indicated in the Location List Report in Appendix IV. These locations within the assessed area were not accessible to the surveyor and are therefore not included in the report.

4.0 FINDINGS

The following section summarizes the findings of the assessment and provides a general description of the asbestos-containing materials (ACM) identified and their locations. For details on approximate quantities, condition, friability, accessibility and locations of asbestos materials; refer to the Asbestos Material Summary Report and All Data Report in Appendix V and VI.

4.1 Excluded Asbestos Materials

A number of materials which might contain asbestos were not sampled during this assessment due to limitations in scope and methodology. Where present, these materials are assumed to contain asbestos until otherwise proven by sampling and analysis. These materials are not shown on the drawings in Appendix I. Excluded materials presumed to contain asbestos include:


- Roofing felts and tar, mastics
- Floor levelling compound
- Ceramic tile setting compound
- Elevator and lift brakes
- Electrical components
- Mechanical packing, ropes and gaskets
- Vermiculite
- Adhesives and duct mastics
- Caulking and putties
- Fibre-reinforced paints and coatings
- Paper products
- Soffit and fascia boards
- Fire resistant doors
- Vibration dampers on HVAC equipment
- Ropes and gaskets in cast-iron bell and spigot joints
- Sealants on pipe threads




4.2 Summary of Building Materials


This section includes a summary of building materials that have been confirmed asbestos-containing by sample analysis, presumed asbestos-containing by visual identification, or confirmed non-asbestos by sampling or based on the manufacture date and known end of use of asbestos in these products.

The locations of samples from historical assessments performed by Pinchin, have been included on the drawings.

Appendix II presents the asbestos bulk sample analytical results.

| Material and Application | Asbestos Type | Photo |
|---|---------------|---|
| Texture finish is present on the Exterior soffit (Location 1000). | None | |
| Parging cement is present on pipe fittings (elbows, valves, tees, hangers etc.). | Chrysotile |  |
| Remaining pipes are either uninsulated or insulated with non-asbestos fibreglass or elastomeric insulation (Armaflex). | None | |
| Ducts are either uninsulated or insulated with non-asbestos fibreglass (foil-faced or canvas). | None | |
| Mechanical equipment is either uninsulated or insulated with non-asbestos fibreglass. | None | |
| All ceiling tiles are non-asbestos from previous sampling or presumed to be non-asbestos based on the date of manufacture determined from the date stamp applied to the top of the tiles. | None | |

| Material and Application | Asbestos Type | Photo |
|---|--|--|
| Drywall joint compound is present on wall and ceiling finishes. | Chrysotile |  |
| Vinyl floor tiles, 12"x12", dark green with white streaks, are present. | Chrysotile (tile) Chrysotile (mastic) |  |
| Vinyl floor tiles, 12"x12", various colours, are present. | Presumed (tile) Presumed (mastic) |  |
| Textile vibration damper is present. | Presumed | |

| Material and Application | Asbestos Type | Photo |
|--|---------------|--|
| Black and gold sink undercoating is present. | Presumed |  |
| Transite (asbestos cement) is present as rainwater leaders. | Presumed | |
| Grey window putty is present between glazing and frames on exterior windows (Location 1000). | Chrysotile | |
| Remaining caulking and putty associated with windows throughout the site were determined to be non-asbestos by analysis. | None | |

Additional notes on the drywall joint compound discussed above:

- Drywall (gypsum board) and drywall joint compound is present as a wall and ceiling finish throughout the building. As per the methodology, drywall joint compound is sampled at exterior walls, columns or other locations that are unlikely to have been renovated in an attempt to determine the presence of asbestos in the original drywall compound. A total of nine samples of drywall joint compound were collected (samples S0001A-C, S0002A-C, S0003A-C, lab reference no. 71921025) and it was found that four samples contained chrysotile asbestos. The asbestos-positive results indicate that at minimum, the original drywall joint compound application contains asbestos and all drywall joint compound should be presumed to contain asbestos. Further sampling may be considered in an attempt to delineate asbestos-containing drywall compound from newer, non-asbestos drywall compound.

Additional notes on the caulking and window putty discussed above:

- Samples of caulking and window putty were collected and analyzed during a project-specific assessment. Remaining caulking and window putty in the building was not included in this assessment due to limitations in scope and methodology. Where present, other caulking and



window putty not sampled is assumed to contain asbestos until otherwise proven by sampling and analysis.

5.0 RECOMMENDATIONS

5.1 General

Perform a detailed intrusive assessment prior to maintenance work, building renovation or demolition operations. The assessment should include destructive testing (e.g., coring and/or removal of building finishes and components), and other hazardous materials (lead, mercury, PCBs, mould, etc.) and materials not tested in this study (e.g., roofing materials, caulking, mastics).

5.2 Remedial Work

No remedial work is recommended.

5.3 On-going Management and Maintenance

The following recommendations are made regarding on-going management and maintenance work involving the asbestos materials identified.

Maintain the Asbestos Management Program (AMP).

Perform a reassessment of asbestos materials on an annual basis.

Remove asbestos-containing materials (ACM) prior to alteration or maintenance work if ACM may be disturbed by the work. Follow appropriate asbestos precautions for the classification of work being performed.

Sample presumed ACM prior to alteration or maintenance work if the presumed ACM may be disturbed by the work.

Update the asbestos inventory report upon completion of any abatement and removal of asbestos-containing materials.

6.0 TERMS AND LIMITATIONS

This work was performed subject to the Terms and Limitations presented or referenced in the proposal for this project.

Information provided by Pinchin is intended for Client use only. Pinchin will not provide results or information to any party unless disclosure by Pinchin is required by law. Any use by a third party of reports or documents authored by Pinchin or any reliance by a third party on or decisions made by a third party based on the findings described in said documents, is the sole responsibility of such third parties.



Pinchin accepts no responsibility for damages suffered by any third party as a result of decisions made or actions conducted. No other warranties are implied or expressed.

7.0 REFERENCES

The following legislation and documents were referenced in completing the assessment and this report:

1. Asbestos on Construction Projects and in Buildings and Repair Operations, Ontario Regulation 278/05.
2. Designated Substances, Ontario Regulation 490/09.
3. Ministry of the Environment Regulation, R.R.O. 1990 Reg. 347 as amended.

\\PIN-HAM-FS02\job\320000s\0320582.000 HWCDSD,Various2023Projects,ASB,CONS\0320582.004 HWCDSD,AllSites,2023,ASB,ASSMT\Deliverables\St. Charles Mountain\Deliverables\320582.004 Asbestos Asmnt Report St. Charles Mountain HWCDSD Aug 31 2023.docx

Template: Master Report for Asbestos Assessment, HAZ, July 29, 2021


APPENDIX I
Drawings

ASBESTOS-CONTAINING DRYWALL JOINT COMPOUND IS PRESENT ON WALL AND CEILING FINISHES THROUGHOUT THE BUILDING.

NOT ALL KNOWN OR SUSPECTED ASBESTOS BUILDING MATERIALS MAY BE DEPICTED ON THE DRAWING. REFER TO THE ASBESTOS ASSESSMENT REPORT FOR A COMPLETE LIST OF KNOWN AND SUSPECTED ASBESTOS BUILDING MATERIALS.

LEGEND IS COLOUR DEPENDENT. NON-COLOUR COPIES MAY ALTER INTERPRETATION.

BASE PLAN PROVIDED BY CLIENT.



905-577-6206

www.pinchin.com

LEGEND:

- (X) LOCATION NUMBER
- ◎ ASBESTOS BULK SAMPLE

ASBESTOS-CONTAINING MATERIALS:

- P PIPE INSULATION
- VINYL FLOOR TILES AND MASTIC
- S SINK UNDERCOATING
- VD VIBRATION DAMPER
- T TRANSITE

NOTE:

ASBESTOS-CONTAINING MATERIALS NOT HATCHED:
 - DRYWALL JOINT COMPOUND ON WALLS AND CEILING
 - WINDOW PUTTY SEALANT

CLIENT:



LOCATION:

ST. CHARLES MOUNTAIN
 150 EAST 5TH STREET
 HAMILTON, ONTARIO

TITLE:

ASBESTOS ASSESSMENT
 FLOOR LEVEL 1

DATE:

AUGUST 2023

PROJECT #:

320582.004

DRAWN BY:

EB

DRAWING:


1 OF 2

CHECKED BY:

EB

SCALE:

NTS




ASBESTOS-CONTAINING DRYWALL JOINT COMPOUND IS PRESENT ON WALL AND CEILING FINISHES THROUGHOUT THE BUILDING.

NOT ALL KNOWN OR SUSPECTED ASBESTOS BUILDING MATERIALS MAY BE DEPICTED ON THE DRAWING. REFER TO THE ASBESTOS ASSESSMENT REPORT FOR A COMPLETE LIST OF KNOWN AND SUSPECTED ASBESTOS BUILDING MATERIALS.

LEGEND IS COLOUR DEPENDENT. NON-COLOUR COPIES MAY ALTER INTERPRETATION.



BASE PLAN PROVIDED BY CLIENT.








905-577-6206

www.pinchin.com

LEGEND:


-  LOCATION NUMBER
-  ASBESTOS BULK SAMPLE

ASBESTOS-CONTAINING MATERIALS:

-  PIPE INSULATION
-  VINYL FLOOR TILES AND MASTIC
-  SINK UNDERCOATING
-  VIBRATION DAMPER
-  TRANSITE

NOTE:

ASBESTOS-CONTAINING MATERIALS NOT HATCHED:
 - DRYWALL JOINT COMPOUND ON WALLS AND CEILING
 - WINDOW PUTTY SEALANT



CLIENT:



LOCATION:

ST. CHARLES MOUNTAIN
 150 EAST 5TH STREET
 HAMILTON, ONTARIO

TITLE:

ASBESTOS ASSESSMENT
 FLOOR LEVEL 2

DATE:

AUGUST 2023

PROJECT # :

320582.004

DRAWN BY:

EB

DRAWING:

2 OF 2

CHECKED BY:

EB

SCALE:

NTS

APPENDIX II
Asbestos Analytical Certificates



Pinchin Ltd. Asbestos Laboratory Certificate of Analysis

Project Name: Hamilton-Wentworth Catholic School Board, St. Charles Mountain,
150 East 5th Street, Hamilton, Ontario

Project No.: 0272113.000

Prepared For: E. Balfour / M. Maiorana

Lab Reference No.: b230653

Analyst(s): K. Cockburn

Date Received: May 21, 2020

Date Analyzed: May 28, 2020

Samples submitted: 3

Phases analyzed: 1

Method of Analysis:

EPA 600/R-93/116 - Method for the Determination of Asbestos in Bulk Building Materials dated July, 1993

Bulk samples are checked visually and scanned under a stereomicroscope. Slides are prepared and observed under a Polarized Light Microscope (PLM) at magnifications of 40X, 100X or 400X as appropriate. Asbestos fibres are identified by a combination of morphology, colour, refractive index, extinction, sign of elongation, birefringence and dispersion staining colours. A visual estimate is made of the percentage of asbestos present. A reported concentration of less than (<) the regulatory threshold (see chart below) indicates the presence of confirmed asbestos in trace quantities, limited to only a few fibres or fibre bundles in an entire sample. This method complies with provincial regulatory requirements where applicable. Multiple phases within a sample are analyzed and reported separately.

All bulk samples submitted to this laboratory for asbestos analysis are retained for a minimum of three months. Samples may be retrieved, upon request, for re-examination at any time during that period.

The Pinchin Ltd. Mississauga asbestos laboratory is accredited by the National Institute of Standards and Technology, National Voluntary Laboratory Accreditation Program (NVLAP Lab Code 101270-0) for the 'EPA – 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples,' and the 'EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials'; and meets all requirements of ISO/IEC 17025:2005.

This report relates only to the items tested.

NOTE: *This test report may not be reproduced, except in full, without the written approval of the laboratory. The client may not use this report to claim product endorsement by NVLAP or any agency of the U.S. Government. This report is valid only when signed in blue ink by the analyst. Vinyl asbestos floor tiles contain very fine fibres of asbestos and may be missed by some laboratories using the PLM method. Internal verification studies performed by Pinchin indicate that the chance of missing asbestos in floor tiles is no higher than about 2%. The vinyl tile study and laboratory documentation on measurement uncertainty is available upon request. The analysis of dust samples by PLM cannot be used as an indicator of past or present airborne asbestos fibre levels.*



Pinchin Ltd. Asbestos Laboratory
Certificate of Analysis

Project Name: Hamilton-Wentworth Catholic School Board, St. Charles Mountain,
150 East 5th Street, Hamilton, Ontario
Project No.: 0272113.000
Prepared For: E. Balfour / M. Maiorana
Lab Reference No.: b230653
Date Analyzed: May 28, 2020

BULK SAMPLE ANALYSIS

| SAMPLE IDENTIFICATION | SAMPLE DESCRIPTION | % COMPOSITION (VISUAL ESTIMATE) | |
|---|---|---------------------------------|-----------------------------|
| | | ASBESTOS | OTHER |
| S0004A Parging cement, Women's Washroom, Location 1003 | Homogeneous, grey, soft, parging cement. | Chrysotile 50-75% | Non-Fibrous Material 25-50% |
| S0004B Parging cement, Corridor, Location 1004 | | | Not Analyzed |
| Comments: | Analysis was stopped due to a previous positive result. | | |
| S0004C Parging cement, Classroom, Location 1017 | | | Not Analyzed |
| Comments: | Analysis was stopped due to a previous positive result. | | |

Reviewed by:

Reporting Analyst:



Analyzed by: *JC*
 Reviewed by: *HB*
 Report Sent by: *HB*

Instructions:

**Pinchin Ltd. - Asbestos Laboratory
 Internal Asbestos Bulk Sample Chain of Custody**

| | | | |
|---|--|-------------------------|--|
| Client Name: | Hamilton-Wentworth Catholic School Board | Project Address: | 150 East 5th Street, Hamilton, Ontario |
| Portfolio/Building No: | St. Charles Mountain | Pinchin File: | 272113 |
| Submitted by: | Emily Balfour | Email: | ebalfour@pinchin.com |
| CC Results to: | Michael Maiorana | CC Email: | mmaiorana@pinchin.com |
| Invoice to: | Accounts Payable | Invoice Email: | ap@pinchin.com |
| Date Submitted: | May 19 2020 | Required by: | May 26 2020 |
| # of Samples: | | Priority: | 5 Day Turnaround |
| Year of Building Construction (Mandatory Field): | 1972 | | |
| Do NOT Stop on Positive (Sample Numbers): | | | |
| Pinchin Group Company (Mandatory Field): | Pinchin | | |

To be Completed by Lab Personnel Only:

| | | | | | |
|-------------------------------|------------------|--------------|---------------|-----------|-----------|
| Lab Reference #: | <i>023065301</i> | Time: | 24 hour clock | | |
| Received by: | | Date: | Month | Day | Year |
| Name(s) of Analyst(s): | | <i>JC</i> | <i>2020</i> | <i>05</i> | <i>28</i> |

| Sample Prefix | Sample No. | Sample Suffix | Sample Description/Location (Mandatory) |
|---------------|------------|---------------|---|
| | S0004 | A | Parging cement, Women's Washroom, Location 1003 <i>CH 5075?</i> |
| | S0004 | B | Parging cement, Corridor, Location 1004 <i>- NA -</i> |
| | S0004 | C | Parging cement, Classroom, Location 1017 <i>- NA -</i> |



Pinchin Ltd. Asbestos Laboratory Certificate of Analysis

Project Name: Hamilton-Wentworth Catholic School Board,
St. Charles Mountain, 150 East 5th Street, Hamilton, Ontario

Project No.: 0272113.002

Prepared For: E. Balfour / M. Maiorana

Lab Reference No.: b234629

Analyst(s): W. Mirza /
C. Luong

Date Received: July 28, 2020

Date Analyzed: July 31, 2020

Samples submitted: 21

Phases analyzed: 19

Method of Analysis:

EPA 600/R-93/116 - Method for the Determination of Asbestos in Bulk Building Materials dated July, 1993

Bulk samples are checked visually and scanned under a stereomicroscope. Slides are prepared and observed under a Polarized Light Microscope (PLM) at magnifications of 40X, 100X or 400X as appropriate. Asbestos fibres are identified by a combination of morphology, colour, refractive index, extinction, sign of elongation, birefringence and dispersion staining colours. A visual estimate is made of the percentage of asbestos present. A reported concentration of less than (<) the regulatory threshold (see chart below) indicates the presence of confirmed asbestos in trace quantities, limited to only a few fibres or fibre bundles in an entire sample. This method complies with provincial regulatory requirements where applicable. Multiple phases within a sample are analyzed and reported separately.

All bulk samples submitted to this laboratory for asbestos analysis are retained for a minimum of three months. Samples may be retrieved, upon request, for re-examination at any time during that period.

The Pinchin Ltd. Mississauga asbestos laboratory is accredited by the National Institute of Standards and Technology, National Voluntary Laboratory Accreditation Program (NVLAP Lab Code 101270-0) for the 'EPA – 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples,' and the 'EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials'; and meets all requirements of ISO/IEC 17025:2005.

This report relates only to the items tested.

NOTE: *This test report may not be reproduced, except in full, without the written approval of the laboratory. The client may not use this report to claim product endorsement by NVLAP or any agency of the U.S. Government. This report is valid only when signed in blue ink by the analyst. Vinyl asbestos floor tiles contain very fine fibres of asbestos and may be missed by some laboratories using the PLM method. Internal verification studies performed by Pinchin indicate that the chance of missing asbestos in floor tiles is no higher than about 2%. The vinyl tile study and laboratory documentation on measurement uncertainty is available upon request. The analysis of dust samples by PLM cannot be used as an indicator of past or present airborne asbestos fibre levels.*



Pinchin Ltd. Asbestos Laboratory Certificate of Analysis

Project Name: Hamilton-Wentworth Catholic School Board,
 St. Charles Mountain, 150 East 5th Street, Hamilton, Ontario
Project No.: 0272113.002
Prepared For: E. Balfour / M. Maiorana

Lab Reference No.: b234629
Date Analyzed: July 31, 2020

BULK SAMPLE ANALYSIS

| SAMPLE IDENTIFICATION | SAMPLE DESCRIPTION | % COMPOSITION (VISUAL ESTIMATE) | |
|---|---|---------------------------------|---|
| | | ASBESTOS | OTHER |
| S0005A Textured plaster soffit, Exterior, Location 1000 | 2 Phases: a) Homogeneous, light grey, hard, cementitious material. | None Detected | Perlite 10-25% Other Non-Fibrous > 75% |
| | b) Homogeneous, white, hard, cementitious material. | Chrysotile < 0.5% | Non-Fibrous Material > 75% |
| S0005B Textured plaster soffit, Exterior, Location 1000 | 2 Phases: a) Homogeneous, light grey, hard, cementitious material. | None Detected | Perlite 10-25% Other Non-Fibrous > 75% |
| | b) Homogeneous, white, hard, cementitious material. | Chrysotile < 0.5% | Non-Fibrous Material > 75% |
| Comments: | Phase a) is small in size. | | |
| S0005C Textured plaster soffit, Exterior, Location 1000 | Homogeneous, white, hard, cementitious material. | Chrysotile < 0.5% | Non-Fibrous Material > 75% |
| Comments: | There is no light grey cementitious material in this sample to be analyzed. | | |
| S0006A Grey window putty, Exterior, Location 1000 | Homogeneous, grey, soft, sticky and rubbery material. | Chrysotile 5-10% | Non-Fibrous Material > 75% |
| S0006B Grey window putty, Exterior, Location 1000 | | | Not Analyzed |
| Comments: | Analysis was stopped due to a previous positive result. | | |



**Pinchin Ltd. Asbestos Laboratory
Certificate of Analysis**

Project Name: Hamilton-Wentworth Catholic School Board,
St. Charles Mountain, 150 East 5th Street, Hamilton, Ontario
Project No.: 0272113.002
Prepared For: E. Balfour / M. Maiorana
Lab Reference No.: b234629
Date Analyzed: July 31, 2020

BULK SAMPLE ANALYSIS

| SAMPLE IDENTIFICATION | SAMPLE DESCRIPTION | % COMPOSITION (VISUAL ESTIMATE) | |
|---|---|---------------------------------|----------------------------|
| | | ASBESTOS | OTHER |
| S0006C Grey window putty, Exterior, Location 1000 | | | Not Analyzed |
| Comments: | Analysis was stopped due to a previous positive result. | | |
| S0007A Brown caulking around window frame, Exterior, Location 1000 | Homogeneous, dark brown, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |
| S0007B Brown caulking around window frame, Exterior, Location 1000 | Homogeneous, dark brown, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |
| S0007C Brown caulking around window frame, Exterior, Location 1000 | Homogeneous, dark brown, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |
| S0008A Black window putty, Exterior, Location 1000 | Homogeneous, black, soft, rubbery material. | None Detected | Non-Fibrous Material > 75% |
| S0008B Black window putty, Exterior, Location 1000 | Homogeneous, black, soft, rubbery material. | None Detected | Non-Fibrous Material > 75% |
| S0008C Black window putty, Exterior, Location 1000 | Homogeneous, black, soft, rubbery material. | None Detected | Non-Fibrous Material > 75% |



Pinchin Ltd. Asbestos Laboratory
Certificate of Analysis

Project Name: Hamilton-Wentworth Catholic School Board,
St. Charles Mountain, 150 East 5th Street, Hamilton, Ontario
Project No.: 0272113.002
Prepared For: E. Balfour / M. Maiorana

Lab Reference No.: b234629
Date Analyzed: July 31, 2020

BULK SAMPLE ANALYSIS

| SAMPLE IDENTIFICATION | SAMPLE DESCRIPTION | % COMPOSITION (VISUAL ESTIMATE) | |
|--|---|---------------------------------|----------------------------|
| | | ASBESTOS | OTHER |
| S0009A White caulking around window frame, Cafeteria A, Location 1039 | Homogeneous, white, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |
| S0009B White caulking around window frame, Classroom, Location 2004 | Homogeneous, white, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |
| S0009C White caulking around window frame, English/Soial Science, Location 1035 | Homogeneous, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |
| S0010A Grey window putty, Classroom, Location 2004 | Homogeneous, grey, soft, sticky and rubbery material. | Chrysotile 5-10% | Non-Fibrous Material > 75% |
| S0010B Grey window putty, Classroom, Location 2004 | | | Not Analyzed |
| Comments: | Analysis was stopped due to a previous positive result. | | |
| S0010C Grey window putty, Classroom, Location 2009 | | | Not Analyzed |
| Comments: | Analysis was stopped due to a previous positive result. | | |
| S0011A Grey caulking around window frame, Exterior, Location 1000 | Homogeneous, grey, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |



Pinchin Ltd. Asbestos Laboratory
Certificate of Analysis

Project Name: Hamilton-Wentworth Catholic School Board,
St. Charles Mountain, 150 East 5th Street, Hamilton, Ontario
Project No.: 0272113.002
Prepared For: E. Balfour / M. Maiorana
Lab Reference No.: b234629
Date Analyzed: July 31, 2020

BULK SAMPLE ANALYSIS

| SAMPLE IDENTIFICATION | SAMPLE DESCRIPTION | % COMPOSITION (VISUAL ESTIMATE) | |
|--|---|---------------------------------|----------------------------|
| | | ASBESTOS | OTHER |
| S0011B Grey caulking around window frame, Exterior, Location 1000 | Homogeneous, grey, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |
| S0011C Grey caulking around window frame, Exterior, Location 1000 | Homogeneous, grey, soft, rubbery caulking material. | None Detected | Non-Fibrous Material > 75% |

Reviewed by:

Reporting Analyst:



WM
Reviewed by: RL
Report Sent by: KC



Instructions:

**Pinchin Ltd. - Asbestos Laboratory
Internal Asbestos Bulk Sample Chain of Custody**

| | | | |
|--|--|------------------|--|
| Client Name: | Hamilton-Wentworth Catholic School Board | Project Address: | 150 East 5th Street, Hamilton, Ontario |
| Portfolio/Building No: | St. Charles Mountain | Pinchin File: | 272113.002 |
| Submitted by: | Emily Balfour | Email: | ebalfour@pinchin.com |
| CC Results to: | Michael Maiorana | CC Email: | mmaiorana@pinchin.com |
| Invoice to: | Accounts Payable | Invoice Email: | ap@pinchin.com |
| Date Submitted: | July 27 2020 | Required by: | July 30 2020 |
| # of Samples: | 21 | Priority: | 3 Day Turnaround |
| Year of Building Construction (Mandatory Field): | 1972 | | |
| Do NOT Stop on Positive (Sample Numbers): | | | |
| Pinchin Group Company (Mandatory Field): | Pinchin | | |

To be Completed by Lab Personnel Only:

| | | | | | |
|------------------------|----------------|-----------------------|---------------|-----|------|
| Lab Reference #: | <u>D234629</u> | Time: | 24 hour clock | | |
| Received by: | <u>RS</u> | Date: | Month | Day | Year |
| Name(s) of Analyst(s): | <u>CL/WM</u> | <u>July 31 / 2020</u> | | | |

| Sample Prefix | Sample No. | Sample Suffix | Sample Description/Location (Mandatory) |
|---------------|------------|---------------|--|
| <u>CL</u> | S0005 | A | Textured plaster soffit, Exterior, Location 1000 <u>a) NO b) CH < 0.5%</u> |
| | S0005 | B | Textured plaster soffit, Exterior, Location 1000 <u>a) NO b) CH < 0.5%</u> |
| | S0005 | C | Textured plaster soffit, Exterior, Location 1000 <u>CH < 0.5%</u> |
| | S0006 | A | Grey window putty, Exterior, Location 1000 <u>CH 5-10%</u> |
| | S0006 | B | Grey window putty, Exterior, Location 1000 <u>- NA -</u> |
| | S0006 | C | Grey window putty, Exterior, Location 1000 <u>- NA -</u> |

6



| Sample Prefix | Sample No. | Sample Suffix | Sample Description/Location (Mandatory) |
|---------------|------------|---------------|--|
| | S0007 | A | Brown caulking around window frame, Exterior, Location 1000 ND |
| | S0007 | B | Brown caulking around window frame, Exterior, Location 1000 ND |
| | S0007 | C | Brown caulking around window frame, Exterior, Location 1000 ND |
| | S0008 | A | Black window putty, Exterior, Location 1000 ND |
| | S0008 | B | Black window putty, Exterior, Location 1000 ND |
| | S0008 | C | Black window putty, Exterior, Location 1000 ND |
| | S0009 | A | White caulking around window frame, Cafeteria A, Location 1039 ND |
| | S0009 | B | White caulking around window frame, Classroom, Location 2004 ND |
| | S0009 | C | White caulking around window frame, English/Soial Science, Location 1035 ND |
| | S0010 | A | Grey window putty, Classroom, Location 2004 CH 5-10' |
| | S0010 | B | Grey window putty, Classroom, Location 2004 -NA- |
| | S0010 | C | Grey window putty, Classroom, Location 2009 -NA- |
| | S0011 | A | Grey caulking around window frame, Exterior, Location 1000 ND |
| | S0011 | B | Grey caulking around window frame, Exterior, Location 1000 NP |
| | S0011 | C | Grey caulking around window frame, Exterior, Location 1000 ND |

13

APPENDIX III
Methodology

1.0 GENERAL

An inspection was conducted to identify the asbestos-containing materials (ACM) incorporated in the structure and its finishes as defined by the scope of work.

Information regarding the location and condition of ACM encountered and visually estimated quantities were recorded. The locations of any samples collected were recorded on small-scale plans. As-built drawings and previous reports were referenced where provided.

Sample collection (where performed) was conducted in accordance with our Standard Operating Procedures.

The inspection for asbestos included friable and non-friable asbestos-containing materials (ACM). A friable material is a material that when dry can be crumbled, pulverized or powdered by hand pressure.

Where samples were collected, a separate set of samples was collected of each type of homogenous material suspected to contain asbestos. A homogenous material is defined by the US EPA as material that is uniform in texture and appearance, was installed at one time, and is unlikely to consist of more than one type or formulation of material. The homogeneous materials were determined by visual examination and available information on the phases of construction and prior renovations.

Where samples were collected, samples were collected at a rate that is in compliance with the requirements of local regulations and guidelines. The sampling strategy was also based on known ban dates and phase out dates of the use of asbestos; sampling of certain building materials is not conducted after specific construction dates. In addition, to be conservative, several years past these dates are added to account for some uncertainty in the exact start / finish date of construction and associated usage of ACM. In some cases, manufactured products such as asbestos cement pipe were visually identified without sample confirmation.

Where samples were collected, the asbestos analysis was completed using a stop-positive approach. Only one result meeting the regulated criteria was required to determine that a material is asbestos-containing, but all samples must be analyzed to conclusively determine that a material is non-asbestos. The laboratory stopped analyzing samples from a homogeneous material once a result equal to or greater than the regulated criteria is detected in any of the samples of that material. All samples of a homogeneous material were analyzed if no asbestos is detected. In some cases, all samples were analyzed in the sample set regardless of result.

Where samples were collected, the analysis was performed in accordance with Test Method EPA/600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials, July 1993.

Where samples were collected, analytical results were compared to the following criteria.



| Jurisdiction* | Friable | Non-Friable |
|----------------------|----------------|--------------------|
| Ontario | 0.5% | 0.5% |

Where building materials are described in the report as “non-asbestos” or “does not contain asbestos”, this means that either no asbestos was detected by the analytical method utilized in any of the multiple samples or, if detected, it is below the lower limit of an asbestos-containing material in the applicable regulation. Additionally, these terms are used for materials which historically are known to not include asbestos in their manufacturing.

Asbestos materials were evaluated in order to make recommendations regarding remedial work. The priority for remedial action was based on several factors:

- Friability (friable or non-friable);
- Condition (good, fair, poor, debris);
- Accessibility (ranking from accessible to all building users to inaccessible);
- Visibility (whether the material is obscured by other building components).
- Efficiency of the work (for example, if damaged ACM is being removed in an area, it may be most practical to remove all ACM in the area even if it is in good condition).

For a complete description of the Evaluation Criteria and Basis of Recommendations, refer to Annex A.

METHODOLOGY ANNEX A EVALUATION CRITERIA

EVALUATION CRITERIA AND BASIS OF RECOMMENDATIONS

The detailed asbestos assessment provides information regarding the location, condition, accessibility and friability of the asbestos-containing materials (ACM). In order to make recommendations for compliance with current regulations, Pinchin developed the following criteria.

EVALUATION OF CONDITION

Friable Sprayed or Trowelled Fireproofing, Thermal Insulation and Texture Finishes (Surfacing Materials)

To evaluate the condition of ACM sprayed or trowelled on fireproofing, sprayed or trowelled thermal insulation (non-mechanical), or texture, decorative or acoustic finishes, the following criteria are applied:

| | |
|-------------|---|
| Good | Surface of material shows no significant signs of damage, deterioration or delamination. Good condition includes unencapsulated or unpainted fireproofing or texture finishes, where no or limited delamination or damage is observed, or encapsulated fireproofing or texture finishes where the encapsulant or paint has been applied after the damage or fallout occurred. |
| Poor | A sprayed material that shows signs of significant damage or is significantly delaminating or deteriorating. This may be limited to surface delamination or some portion of the substrate may be exposed. |

In Locations where damage exists in isolated areas, both good and poor condition may be applicable. The extent of each condition will be recorded. Fair condition is not utilized in the evaluation of ACM sprayed or trowelled fireproofing, sprayed or trowelled thermal insulation (non-mechanical), or texture, decorative or acoustic finishes.

The evaluation of the above products above ceilings may be limited by the number of observations and by building components such as ducts or full height walls that obstruct the above ceiling observations.

Friable Mechanical or Thermal System Insulation (TSI)

To evaluate the condition of mechanical insulation on vessels, boilers, breeching, ducts, pipes, fan units, equipment etc. the following criteria are applied:

| | |
|-------------|---|
| Good | Insulation is completely covered in jacketing and exhibits no evidence of damage or deterioration. No insulation is exposed. Includes conditions where the jacketing has minor damage (i.e. scuffs or stains), but the jacketing is not penetrated. |
| Fair | Minor penetrating damage to jacketed insulation (cuts, tears, nicks, deterioration or delamination) or undamaged insulation that has never been jacketed. Insulation is exposed but not showing surface disintegration. The extent of missing insulation ranges from minor to none. Damage can be repaired. |

| | |
|-------------|---|
| Poor | Original insulation jacket is missing, damaged, deteriorated or delaminated. Insulation is exposed and significant areas have been dislodged. Damage cannot be readily repaired. Includes components where insulation may have been removed incompletely. |
|-------------|---|

The evaluation of mechanical insulation may be limited by the number of observations made and building components such as ducts or full height walls that obstruct observations. It is often not possible to observe each foot of mechanical insulation from all angles.

Potentially Friable Materials and Miscellaneous Friable Materials

Potentially friable ACM are products that are basically non-friable while in place but have the potential to generate friable dust upon removal or if significantly disturbed without appropriate procedures. These products may become friable if damaged. Potentially friable materials include materials such as acoustic ceiling tiles and plaster. To evaluate the condition of potentially friable materials, the following criteria are applied:

| | |
|-------------|--|
| Good | No significant damage or deterioration. Still serving its intended use as a building material or finish. |
| Fair | Showing signs of some cracking or breakage, but is not deteriorating (e.g. cracked plaster, broken but in place ceiling tile, missing tile or section of plaster etc.). The condition is such that it is still serving its intended use as a building material or finish but may require repair for mainly cosmetic purposes. |
| Poor | Significant deterioration or breaking apart of the material. Material has deteriorated to the point it is not serving its intended use as building material or finish. Material has deteriorated to a point it has become friable. Normally potentially friable ACM in Poor condition is not repairable and requires at least localized removal and replacement. |

Non-Friable Materials

Non-friable ACM cover a wide range of products with a wide variation in their tendency to release dust or asbestos fibres to the air. Many of these materials, (particularly where the matrix is an unweathered bitumen, asphalt or tar material) do not release fibres except in very unusual circumstances or during significant disturbance (e.g. use of abrasive power tools). Others with a cementitious matrix (asbestos-cement products) can more readily release dust due to abrasion, demolition, weathering, etc. The potential for asbestos release from non-friable ACM is always lower than from friable ACM. To evaluate the condition of non-friable Materials, the following criteria are applied:

| | |
|-------------|--|
| Good | No significant damage or deterioration. Still serving its intended use as a building material or finish. |
|-------------|--|

| | |
|-------------|---|
| Fair | Showing signs of some cracking or breakage but is not deteriorating (e.g. cracked vinyl floor tile, missing piece of tile or transite, etc.). The condition is such that it is still serving its intended use as a building material or finish but may require repair for mainly cosmetic purposes. |
| Poor | Significant deterioration or breaking apart of the material to the point at which it cannot be repaired, and it will require at least local removal. Material has deteriorated to the point it is not serving its intended use as building material or finish. Material may have deteriorated to a point where traffic or disturbance may cause it to become friable. |

Evaluation of ACM Debris

The identification of the exact location or presence of debris on the top of ceiling tiles is limited by the number of observations made and the presence of building components such as ducts or full height walls that obstruct observations.

The presence of fallen or dislodged ACM is noted separately from the ACM source and is referred to as Debris. Debris may be friable if from a friable ACM source or a badly deteriorated non-friable ACM source. Debris may also be non-friable (such as fallen pieces of transite sheet or mastic fittings, or broken, dislodged floor tiles).

| | |
|---------------|--|
| Debris | Debris may be friable or non-friable but is always identified as debris. |
|---------------|--|

Evaluation of Presumed Asbestos-Containing Material (PACM)

Presumed asbestos-containing materials (PACM), are building materials that may contain asbestos but were not sampled or analyzed due to inaccessibility or the need to perform destructive testing to obtain a reasonable sample set. Evaluation of these materials is based on the assumption that these PACM are asbestos-containing.

A list of PACM is provided in the report and they are generally not included in the detailed room by room reports. Typically, they are excluded because they are inaccessible or present in very small quantities. If PACM are evaluated, Pinchin uses the criteria that correspond with the type (and friability) of the material listed above.



EVALUATION OF ACCESSIBILITY

The accessibility of building materials known or suspected of being ACM is rated according to the following criteria:

| | |
|-----------------------------------|--|
| Access (A) | Common areas of the building within reach of all building users (approximately 8' - 9' from floor or standard ceiling height). Includes other areas where occupant activities may result in disturbance of material that is not normally within reach from floor level, but may be disturbed by common activities (e.g. gymnasiums, workshops, warehouses) |
| Access (B) | Areas of the building accessed primarily by Maintenance/Caretaking/Janitorial Staff and within reach without use of a ladder. Includes areas within reach in Boiler Rooms, Electrical Rooms, Janitors Closets, Elevator Rooms, Mechanical Rooms, etc. Includes materials within reach from fixed ladders or catwalks, mezzanines, and accessible pipe chases. |
| Access (C) and Visible | Areas of the building above 8' - 9' where use of a ladder or scaffold is required to reach the ACM. Only includes ACM that are visible to view without the removal or opening of other building components such as ceiling tiles or service access panels. Visible column on HMIS sheets will say YES. |
| Access (C) and not Visible | Areas of the building above 8' - 9' where use of a ladder or scaffold is required to reach the ACM. Includes ACM that are not visible to view and require the removal of a building component to see, such as ceilings tiles or access panels to view and access. Includes rarely entered crawl spaces, attic spaces, etc. Observations will be limited to the extent visible from the access points. Visible column on HMIS sheets will say NO. |
| Access (D) | Areas of the building behind inaccessible solid ceiling systems, walls or equipment etc. where demolition of the ceiling, wall or equipment etc. is required to reach the ACM. Material inaccessible due to height or location or is only accessed under unusual situations. Evaluation of condition and extent of ACM is limited or impossible, depending on the surveyor's ability to visually examine materials in Access D. |

ACTION MATRIX AND DEFINITIONS

Pinchin's evaluation of the viability of a specific asbestos control option is based on the consideration of the friability, condition, accessibility and visibility of a material. The logic used is that damaged ACM located in an area frequently accessed by all building occupants is of a higher priority than damaged ACM located in an infrequently accessed service area. The action matrix considers the potential for fibre release (primarily from friable ACM) and the possible concerns from regulatory bodies and many building occupants to all damaged ACM (including non-friable).

In any building with asbestos, many current regulations require an Asbestos Management Program be implemented. Depending on the condition and the accessibility, more active measures such as repair or removal may be recommended. The following matrix provides guidance for recommended Actions in the absence of renovation or demolition. In the event of construction or maintenance activity which will disturb ACM more aggressive control or removal will be required.

Action Matrix

The following tables outline the action decisions based on the relationship of assessed factors. Table I applies to friable ACM. Table II applies to non-friable ACM.

Table I Decision Matrix for Friable ACM

| Access | Condition | | | Debris |
|-----------------|-----------------------|-----------------------|----------|----------|
| | Good | Fair | Poor | |
| (A) | Action 5 ¹ | Action 5 ² | Action 3 | Action 1 |
| (B) | Action 7 | Action 6 ³ | Action 3 | Action 1 |
| (C) Visible | Action 7 | Action 6 | Action 3 | Action 2 |
| (C) Not Visible | Action 7 | Action 7 | Action 4 | Action 2 |
| (D) | Action 7 | Action 7 | Action 7 | Action 7 |

Table II Decision Matrix for Potentially Friable and Non-Friable ACM

| Access | Condition | | | Debris |
|-----------------|-----------|-----------------------|----------|----------|
| | Good | Fair | Poor | |
| (A) | Action 7 | Action 7 ⁴ | Action 3 | Action 1 |
| (B) | Action 7 | Action 7 | Action 3 | Action 1 |
| (C) Visible | Action 7 | Action 7 | Action 4 | Action 2 |
| (C) Not Visible | Action 7 | Action 7 | Action 4 | Action 2 |
| (D) | Action 7 | Action 7 | Action 7 | Action 7 |

Action Definitions

The following are the definitions in the Action Matrix Table presented above:

Action Definitions

| | |
|-----------------|--|
| Action 1 | Clean-Up of ACM Debris Restrict access that is likely to cause a disturbance of the ACM Debris and clean up ACM Debris. Utilize appropriate asbestos precautions. |
|-----------------|--|

¹ If friable ACM in access (A)/Good condition is not proactively removed Action 7 (Manage) is recommended.

² If friable ACM in access (A)/Fair condition is not proactively removed repair is recommended.

³ If friable ACM in access (B)/Fair condition is likely to be disturbed after repair proactive removal is recommended.

⁴ Action 7 is recommended for all non-friable ACM in Fair condition however some clients may wish to repair or take some action primarily for cosmetic reasons

Action Definitions

| | |
|-----------------|--|
| Action 2 | <p>Precautions for Access Which may Disturb ACM Debris</p> <p>Use appropriate means to isolate the debris or to limit entry to the area which may disturb the material. At locations where ACM Debris can remain in place in lieu of removal or clean-up (e.g. Debris on top of ceiling tiles or behind lockable door), Utilize appropriate asbestos precautions to enter the area if this will disturb debris. The precautions will be required until the ACM Debris has been cleaned up.</p> |
| Action 3 | <p>ACM Removal</p> <p>Remove ACM. Utilize asbestos procedures appropriate to the scope of the removal work. Until it is removed, restrict access to the material so it is not disturbed.</p> |
| Action 4 | <p>Precautions for Work Which may Disturb ACM in Poor Condition. Utilize appropriate asbestos precautions if ACM may be disturbed by work on or near ACM. This does not require restricting access to the area, only control of work which may contact or disturb the ACM. Removal is the only viable option if work will disturb ACM.</p> |
| Action 5 | <p>Proactive ACM Removal</p> <p>Remove friable ACM where the presence of friable asbestos in Good condition is not desirable. If friable ACM in Fair condition is not removed, then Repair friable ACM.</p> |
| Action 6 | <p>ACM Repair</p> <p>Repair friable ACM in Fair condition which is not likely to be damaged again or disturbed by normal use of the area or room. Pinchin recommends proactive removal if friable ACM is likely to be damaged or disturbed during normal use of the area or room</p> |
| Action 7 | <p>Asbestos Management Program with Routine Surveillance Implement an Asbestos Management Program, including routine surveillance of ACM. Reassess materials regularly (typically once per year).</p> |

APPENDIX IV
Location List

Client: Hamilton-Wentworth Catholic District Sch
Building Name: St Charles - Mountain Campus
Survey Date: 2018-07-19
Building Phases: A: 1972

Site: 150 East 5th Street, Hamilton, ON
Last Re-Assessment: 2023-07-31

| Location No. | Name or Description | Area ft ² | Floor No. | Bldg. Phase | Notes |
|--------------|--|----------------------|-----------|-------------|---|
| 1 | Presumed Asbestos-Containing Materials | 0 | 0 | A | Where present, these materials are assumed to contain asbestos until otherwise proven by sampling and analysis. |
| 1000 | Exterior | 0 | | A | |
| 1001 | Child Minding | 0 | 1 | A | |
| 1002 | Men's Washroom | 0 | 1 | A | |
| 1003 | Women's Washroom | 0 | 1 | A | |
| 1004 | Corridor | 0 | 1 | A | |
| 1005 | Storage | 0 | 1 | A | |
| 1006 | Principal's Office | 0 | 1 | A | |
| 1007 | Office | 0 | 1 | A | |
| 1008 | Computer Lab | 0 | 1 | A | |
| 1009 | VP Office | 0 | 1 | A | |
| 1010 | Main Office | 0 | 1 | A | |
| 1011 | Financial Analyst | 0 | 1 | A | |
| 1012 | Lunch Room | 0 | 1 | A | |
| 1013 | Stage | 0 | 1 | A | |
| 1014 | Gym | 0 | 1 | A | |
| 1015 | Credit Office | 0 | 1 | A | |
| 1017 | Classroom | 0 | 1 | A | |
| 1018 | Classroom | 0 | 1 | A | |
| 1019 | Classroom | 0 | 1 | A | |
| 1020 | Classroom | 0 | 1 | A | |
| 1021 | Sink Room | 0 | 1 | A | |
| 1022 | Custodian Storage | 0 | 1 | A | |
| 1023 | Storage/Mechanical | 0 | 1 | A | |
| 1024 | Custodian Office | 0 | 1 | A | |
| 1025 | Staff Room | 0 | 1 | A | |
| 1026 | Staff Womens Washroom | 0 | 1 | A | |
| 1027 | YMCA | 0 | 1 | A | |
| 1028 | Photo Copier | 0 | 1 | A | |
| 1029 | Science | 0 | 1 | A | |
| 1030 | English Room | 0 | 1 | A | |
| 1031 | English Room | 0 | 1 | A | |
| 1032 | Business/Computer | 0 | 1 | A | |
| 1033 | Math | 0 | 1 | A | |
| 1034 | Math | 0 | 1 | A | |
| 1035 | English/Social Science | 0 | 1 | A | |
| 1036 | LBS | 0 | 1 | A | |
| 1037 | Kitchen | 0 | 1 | A | |
| 1038 | Cafeteria B and Storage | 0 | 1 | A | |
| 1039 | Cafeteria A | 0 | 1 | A | |
| 1040 | Chef Office | 0 | 1 | A | |
| 1041 | Storage | 0 | 1 | A | |
| 1042 | Custodian | 0 | 1 | A | |
| 1043 | Stairwell | 0 | 1 | A | |
| 1044 | Stairwell | 0 | 1 | A | |
| 1045 | Stairwell | 0 | 1 | A | |
| 1046 | Stairwell | 0 | 1 | A | |
| 1047 | Storage/ Kitchen | 0 | 1 | A | |
| 1048 | Balcony | 0 | 1 | A | |
| 1050 | Storage | 0 | 1 | A | |
| 1051 | Storage | 0 | 1 | A | |
| 1052 | Storage | 0 | 1 | A | |
| 1053 | Corridor | 0 | 1 | A | |
| 1055 | Staff Mens Washroom | 0 | 1 | A | |
| 2000 | Stairwell | 0 | 2 | A | |
| 2001 | Classroom, room no. 25 | 0 | 2 | A | |
| 2002 | Hallway | 0 | 2 | A | |
| 2003 | Classroom, room no. 24 | 0 | 2 | A | |
| 2004 | Classroom | 0 | 2 | A | |
| 2005 | Classroom, room no. 22 | 0 | 2 | A | |
| 2006 | Classroom, room no. 21 | 0 | 2 | A | |

| Location No. | Name or Description | Area ft ² | Floor No. | Bldg. Phase | Notes |
|--------------|-----------------------------|----------------------|-----------|-------------|-------|
| 2007 | Stairwell | 0 | 2 | A | |
| 2008 | Corridor | 0 | 2 | A | |
| 2009 | Classroom, room no. 11 | 0 | 2 | A | |
| 2010 | Corridor | 0 | 2 | A | |
| 2011 | Classroom, room no. 12 | 0 | 2 | A | |
| 2012 | Classroom, room no. 13 | 0 | 2 | A | |
| 2013 | Men's Washroom | 0 | 2 | A | |
| 2014 | Custodian Room | 0 | 2 | A | |
| 2015 | Caretaker Closet | 0 | 2 | A | |
| 2016 | Corridor | 0 | 2 | A | |
| 2017 | ESL Room, room no. A | 0 | 2 | A | |
| 2018 | Copy Room | 0 | 2 | A | |
| 2019 | Spare Room | 0 | 2 | A | |
| 2020 | Classroom, room no. 14 | 0 | 2 | A | |
| 2021 | Corridor | 0 | 2 | A | |
| 2022 | Office | 0 | 2 | A | |
| 2023 | Office | 0 | 2 | A | |
| 2024 | Office | 0 | 2 | A | |
| 2025 | Office | 0 | 2 | A | |
| 2026 | Office | 0 | 2 | A | |
| 2027 | Office | 0 | 2 | A | |
| 2028 | Classroom, room no. 32 | 0 | 2 | A | |
| 2029 | Classroom, room no. 33 | 0 | 2 | A | |
| 2030 | Stairwell, room no. A | 0 | 2 | A | |
| 2031 | Classroom, room no. 17 | 0 | 2 | A | |
| 2032 | Classroom, room no. 16 | 0 | 2 | A | |
| 2033 | Classroom, room no. 15 | 0 | 2 | A | |
| 2034 | Classroom, room no. 20 | 0 | 2 | A | |
| 2035 | Classroom, room no. 19 | 0 | 2 | A | |
| 2036 | Classroom, room no. 18 | 0 | 2 | A | |
| 2037 | Classroom, room no. 26 | 0 | 2 | A | |
| 2038 | Classroom, room no. 27 | 0 | 2 | A | |
| 2039 | Classroom | 28 | 2 | A | |
| 2040 | Corridor | 0 | 2 | A | |
| 2041 | Classroom, room no. 31 | 0 | 2 | A | |
| 2042 | Classroom | 0 | 2 | A | |
| 2043 | Classroom | 0 | 2 | A | |
| 2044 | Eyewash Station, room no. 2 | 0 | 2 | A | |
| 2045 | Womens Washroom | 0 | 2 | A | |
| 2046 | Spare Room | 0 | 2 | A | |

APPENDIX V
Summary Report / Sample Log

Client: Hamilton-Wentworth Catholic District Sch

Site: 150 East 5th Street, Hamilton, ON

Building Name: St Charles - Mountain Campus

Survey Date: 2018-07-19

| HAZMAT | Sample No | System/Component/Material/Sample Description | Locations | Bldg. Phase | LF | SF | EA | % | Type | Positive | Friability |
|----------|-----------|---|--|-------------|----|----|----|-----|--------------------|----------|------------|
| Asbestos | S0001 ABC | Ceiling, Wall, Ceiling Column Drywall And Joint Compound | 1015,1019,1021,1022,1023,1041,1047,2014 | A | 0 | 0 | 0 | 100 | Chrysotile | Yes | NF |
| Asbestos | S0002 ABC | Wall Drywall And Joint Compound | 1004,1006,1007,1008,1010,1011,1012,1015,1018,1028 | A | 0 | 0 | 0 | 100 | Chrysotile | Yes | NF |
| Asbestos | S0003 ABC | Wall Drywall And Joint Compound | 2009,2011,2012 | A | 0 | 0 | 0 | 100 | None Detected | No | |
| Asbestos | S0004 ABC | Piping Parging Cement | 1003,1004,1014,1017,1018,1019,1020,2025 | A | 0 | 0 | 72 | 0 | Chrysotile | Yes | F |
| Asbestos | S0005 ABC | Ceiling Soffit Plaster Textured, Outside Location 1044 | 1000 | A | 0 | 0 | 0 | 0 | Chrysotile | No | |
| Asbestos | S0006 ABC | Other Window Putty Grey | 1000 | A | 0 | 0 | 0 | 33 | Chrysotile | Yes | NF |
| Asbestos | S0007 ABC | Other Window Caulking Brown, Outside Location 1036 | 1000 | A | 0 | 0 | 0 | 0 | None Detected | No | |
| Asbestos | S0008 ABC | Other Window Putty Black, Outside Locations 1007 And 1036 | 1000 | A | 0 | 0 | 0 | 0 | None Detected | No | |
| Asbestos | S0009 ABC | Other Window Caulking White | 1006,1008,1009,1010,1033,1034,1035,1037,1038,1039,2001,2002,2003,2004,2005,2006,2009,2020,2022,2023,2024,2025,2026,2027,2028,2029 | A | 0 | 0 | 0 | 0 | None Detected | No | |
| Asbestos | S0010 ABC | Other Window Putty Grey | 1006,1008,1009,1010,1033,1034,1035,1037,1038,1039,2001,2003,2004,2005,2006,2009,2020,2022,2023,2024,2025,2026,2027,2028,2029 | A | 0 | 0 | 0 | 100 | Chrysotile | Yes | NF |
| Asbestos | S0011 ABC | Other Window Caulking Grey | 1000 | A | 0 | 0 | 0 | 0 | None Detected | No | |
| Asbestos | V9000 | Floor Vinyl Floor Tile And Mastic 12"x 12". Dark Green With White Streak (previously Sampled) | 1005,1017,1018,1020,1024,1039,1047,2015 | A | 0 | 0 | 0 | 100 | Confirmed Asbestos | Yes | NF |
| Asbestos | V9500 | Duct Textile | 1048 | A | 0 | 0 | 0 | 0 | Presumed Asbestos | Yes | NF |
| Asbestos | V9500 | Floor Mastic | 1001,1006,1007,1008,1009,1010,1011,1012,1015,1019,1025,1029,1030,1031,1032,1033,1034,1035,1036,1038,1040,1042,2000,2001,2002,2003,2004,2005,2006,2007,2008,2009,2010,2011,2012,2016,2017,2019,2020,2021,2022,2023,2024,2025,2026,2027,2028,2029,2030,2031,2032,2033,2034,2035,2036,2037,2038,2039,2040,2041,2042,2043,2045 | A | 0 | 0 | 0 | 100 | Presumed Asbestos | Yes | NF |
| Asbestos | V9500 | Floor Vinyl Floor Tile And Mastic 12" X 12" Beige Marble, 12" X 12" Beige Marble, 12" X 12" Dark Grey With White Streaks, Vinyl Floor Tile 12"x 12" Beige Marble, Vinyl Floor Tile 12"x 12" Beige Marble., Vinyl Floor Tile 12"x 12" Beige With Brown Fleck, Vinyl Floor Tile 12"x 12" Beige With Brown Fleck., Vinyl Floor | 1001,1006,1007,1008,1009,1010,1011,1012,1014,1015,1017,1019,1025,1029,1030,1031,1032,1033,1034,1035,1036,1038,1040,1042,2000,2001,2002,2003,2004,2005,2006,2007,2008,2009,2010,2011,2012,2013,2016,2017,2018,2019,2020,2021,2022,2023,2024,2025,2026,2027,2028,2029,2030,2031,2032,2033,2034,2035,2036,2037,2038,2039,2040 | A | 0 | 0 | 0 | 99 | Presumed Asbestos | Yes | NF |

| HAZMAT | Sample No | System/Component/Material/Sample Description | Locations | Bldg. Phase | LF | SF | EA | % | Type | Positive | Friability |
|----------|-----------|--|--|-------------|----|----|----|-----|-------------------|----------|------------|
| | | Tile 12"x 12" Beige With Brown Streak., Vinyl Floor Tile 12"x 12" Beige With Tan Streak., Vinyl Floor Tile 12"x 12" Black With White Fleck., Vinyl Floor Tile 12"x 12" Dark Grey With White Streak., Vinyl Floor Tile 12"x 12" Grey/white Dense Fleck., Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck., Vinyl Floor Tile 12"x 12" White With Black Fleck. | 2041,2042,2043,2045,2046 | | | | | | | | |
| Asbestos | V9500 | Other Sink Mastic, Black Undercoating | 1047 | A | 0 | 0 | 1 | 0 | Presumed Asbestos | Yes | NF |
| Asbestos | V9500 | Other Sink Mastic, Gold Undercoating | 1028 | A | 0 | 0 | 1 | 0 | Presumed Asbestos | Yes | NF |
| Asbestos | V9500 | Other N/a Roofing Felts And Tar, Mastics, Floor Levelling Compound, Ceramic Tile Setting Compound, Elevator And Lift Brakes, Electrical Components, Mechanical Packing, Ropes And Gaskets, Vermiculite, Adhesives And Duct Mastics, Caulking And Putties, Fibre-reinforced Paints And Coatings, Paper Products, Soffit And Fascia Boards, Fire Resistant Doors, Stucco, Plaster Or Other Cementitious Parge Coatings, Vibration Dampers On Hvac Equipment, Terrazzo, Ropes And Gaskets In Cast-iron Bell And Spigot Joints, Sealants On Pipe Threads | 1 | A | 0 | 0 | 0 | 100 | Presumed Asbestos | Yes | NF |
| Asbestos | V9500 | Piping Cement Product | 1017,1019 | A | 20 | 0 | 0 | 0 | Presumed Asbestos | Yes | NF |
| Asbestos | V9500 | Wall Column Drywall And Joint Compound | 1029,1030,1031,1032,1033,1034,1035,1036,2002 2003,2004,2005,2006,2009,2011,2012,2021,2025 2026,2027,2028,2029,2031,2032,2033,2034,2035 2036,2037,2038,2039,2040,2041,2042,2043 | A | 0 | 0 | 0 | 100 | Presumed Asbestos | Yes | NF |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) 2' X 4' Long Fissure Random Pinhole (previously Sampled) | 1027,1028,1050,1051,1053,2000,2008,2009,2011 2012,2013,2015,2016,2017,2018,2019,2045,2046 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) 2' X 4' Long Fissure Random Pinhole. | 1052 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) 2' X 4' Short Fissure Random Pinhole. Date Stamped 2010. | 2007 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) 2' X 4' Small And Irregular Pinhole. Date Stamped 08/23/09. | 1034,1035,1039 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) 2' X 4' Small And Irregular Pinhole. Date Stamped 08/23/09. | 1033,2022 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Acoustic Tile Ceiling Tiles (lay-in) 2' X 4'. Long Fissure Random Pinhole (previously Sampled) | 1005 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |

| HAZMAT | Sample No | System/Component/Material/Sample Description | Locations | Bldg. Phase | LF | SF | EA | % | Type | Positive | Friability |
|----------|-----------|---|--|-------------|----|----|----|-----|--------------|----------|------------|
| Asbestos | V0000 | Ceiling Acoustic Tile Ceiling Tiles (lay-in) 2x4 Small And Irregular Pinhole (date Stamped 08/23/09) | 1055 | A | 0 | 0 | 0 | 0 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) 2x4, Small And Irregular Pinholes. Date Stamped 08/23/09. | 1008 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Long Fissure Random Pinhole. | 2044 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Short Fissure Random Pinhole. | 1017 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Short Fissure Random Pinhole. Date Stamped 2010. | 2029 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Short Fissure Random Pinhole. Date Stamped 1996. | 1015,1019 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Short Fissure Random Pinhole. Date Stamped 2010. | 1050,1051,1052,1053,2001,2003,2004,2005,2006,2008,2010,2026,2030,2031,2032,2033,2034,2035,2036,2037,2038,2039,2040,2041,2042,2043,2044 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Short Fissure Random Pinhole. Date Stamped 1996. | 1018 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Short Fissure Random Pinhole. Date Stamped 2010. | 2002 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Small And Irregular Pinhole. Date Stamped 08/23/09 | 1024,1043 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Acoustic Tile Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Small And Irregular Pinhole. Date Stamped 08/23/09. | 1025,1032,1036,1042,1044,1045,2021,2023,2024,2025,2028 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Small And Irregular Pinhole. Date Stamped 08/23/09 | 1007 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Small And Irregular Pinhole. Date Stamped 08/23/09. | 1009,1010,1011,1012,1026,1029,1038,1040,1046,2020,2027 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4' Textured (previously Sampled) | 1037 | A | 0 | 0 | 0 | 0 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4'. Small And Irregular Pinhole - Date Stamped 08/23/09. | 1001 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4'. Small And Irregular Pinhole - Date Stamped | 1002,1003 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |

| HAZMAT | Sample No | System/Component/Material/Sample Description | Locations | Bldg. Phase | LF | SF | EA | % | Type | Positive | Friability |
|----------|-----------|--|-----------|-------------|----|----|----|-----|--------------|----------|------------|
| | | 08/23/09. | | | | | | | | | |
| Asbestos | V0000 | Ceiling Ceiling Tiles (lay-in) Ceiling Tile 2' X 4'. Small And Irregular Pinhole. Date Stamped 08/23/09. | 1004,1006 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Floor Terrazzo | 1055 | A | 0 | 0 | 0 | 0 | Non Asbestos | No | |
| Asbestos | V0000 | Piping Fibreglass | 1055 | A | 0 | 0 | 0 | 0 | Non Asbestos | No | |
| Asbestos | V0000 | Wall Column Drywall And Joint Compound Hwcdsb Sample Agat 19h455712 | 1032,2001 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |
| Asbestos | V0000 | Wall Masonry | 1007,1055 | A | 0 | 0 | 0 | 100 | Non Asbestos | No | |

Legend:

| Sample number | | Units | | |
|---------------|--|-------|-------------|---------------------------------|
| S#### | Asbestos sample collected | SF | Square feet | NF Non Friable material. |
| L#### | Paint sample collected | LF | Linear feet | F Friable material |
| P#### | PCB sample collected | EA | Each | PF Potentially Friable material |
| M#### | Mould sample collected | % | Percentage | |
| V#### | Material visually similar to numbered sample collected | | | |
| V0000 | Known non Hazardous Material | | | |
| V9000 | Material is visually identified as Hazardous Material | | | |
| V9500 | Material is presumed to be Hazardous Material | | | |
| [Loc. No.] | Abated Material | | | |

APPENDIX VI
HMIS All Data Report

Client: Hamilton-Wentworth Catholic District Sch
Location: #1 : Presumed Asbestos-Containing Materials
Survey Date: 2018-07-19

Site: Adult
Floor: 0

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|---------------|-------------------|--------|-------------------|----|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable | |
| Other | | N/A, Roofing felts and tar, mastics, Floor levelling compound, Ceramic tile setting compound, Elevator and Lift Brakes, Electrical components, Mechanical packing, ropes and gaskets, Vermiculite, Adhesives and duct mastics, Caulking and putties, Fibre-reinforced paints and coatings, Paper products, Soffit and fascia boards, Fire resistant doors, Stucco, plaster or other cementitious parge coatings, Vibration dampers on HVAC equipment, Terrazzo, Ropes and gaskets in cast-iron bell and spigot joints, Sealants on pipe threads | | | D | N | | 100(7) | | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |

Where present, these materials are assumed to contain asbestos until otherwise proven by sampling and analysis.

Client: Hamilton-Wentworth Catholic District Sch
Location: #1000 : Exterior
Survey Date: 2018-07-19

Site: Adult
Floor:

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|-------|------|------|------|----------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | Soffit | Plaster, textured, outside location 1044 | | | C | Y | | | | | | S0005ABC | Chrysotile | <0.5% | None | |
| Other | Window | Caulking, brown, outside location 1036 | | | A | Y | | | | | | S0007ABC | None Detected | N.D. | None | |
| Other | Window | Caulking, grey | | | A | Y | | | | | | S0011ABC | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 33(7) | | | % | S0006ABC | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Other | Window | Putty, black, outside locations 1007 and 1036 | | | A | Y | | | | | | S0008ABC | None Detected | N.D. | None | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1001 : Child Minding
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|----------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4'. Small and Irregular Pinhole - Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Insulation | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | 100 | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1002 : Men's Washroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4'. Small and Irregular Pinhole - Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1003 : Women's Washroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4'. Small and Irregular Pinhole - Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Piping | | Parging Cement | | | C | N | | 6(7) | | | EA | S0004A | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1004 : Corridor
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4'. Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Piping | | Parging Cement | | | C | N | | 21(7) | | | EA | S0004B | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | S0002C | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1005 : Storage
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|---------------|--|------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | Acoustic Tile | Ceiling Tiles (lay-in), 2' x 4'. Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1006 : Principal's Office
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4'. Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0002 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1007 : Office
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09 | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0002 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1008 : Computer Lab
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2x4, small and irregular pinholes. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0002 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1009 : VP Office
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1010 : Main Office
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0002 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1011 : Financial Analyst
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0002 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1012 : Lunch Room
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Light Grey Multi-fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0002 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1013 : Stage
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|----------|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Steel | | | A | Y | | | | | | | | | | |
| Floor | | Wood | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1014 : Gym
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | Deck | Steel | | | A | Y | | | | | | | | | | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Tan Streak. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | | | | | | | | | |
| Piping | | Parging Cement | | | C | Y | | 15(7) | | | EA | V0004 | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1015 : Credit Office
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 1996. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Ceiling | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0001 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Dark Grey with White Streak. | | | A | Y | | | 1(7) | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" White with Black Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0002 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1017 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|---------------------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Tan Streak. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Piping ¹ | | Cement Product | | | C | N | | 10(7) | | | LF | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Parging Cement | | | C | N | | 12(7) | 4(7) | | EA | S0004C | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

1 - In pipe chase

Client: Hamilton-Wentworth Catholic District Sch
Location: #1018 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|---------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 1996. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Piping | | Parging Cement | Fitting | | C | N | | | | | EA | V0004 | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | S0002A | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1019 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 1996. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" White with Black Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Cement Product | | | C | N | | 10(7) | | | LF | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Parging Cement | | | C | N | | 6(7) | | | EA | V0004 | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | Column | Drywall and joint compound | | | A | Y | | 100(7) | | | % | S0001A | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1020 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 1996. | | | C | Y | | 100 | | | | | | | | |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Piping | | Parging Cement | | | C | N | | 6(7) | | | EA | V0004 | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1021 : Sink Room
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|----------------------------|------|----------|----|----|-----|--------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Drywall and joint compound | | | C | Y | | 100(7) | | | % | V0001 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1022 : Custodian Storage
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|----------------------------|------|----------|----|----|-----|--------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Drywall and joint compound | | | C | Y | | 100(7) | | | % | V0001 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Floor | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1023 : Storage/Mechanical
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|----------------------------|------|----------|----|----|-----|--------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Drywall and joint compound | | | C | Y | | 100(7) | | | % | V0001 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Floor | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1024 : Custodian Office
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09 | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1025 : Staff Room
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fiberglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1026 : Staff Womens Washroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1027 : YMCA
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1028 : Photo Copier
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Other | Sink | Mastic, Gold, undercoating | | | A | N | | 1(7) | | | EA | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | S0002B | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1029 : Science
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1030 : English Room
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1031 : English Room
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | | | | | |
| Floor | | Vinyl Floor Tile and Mastic, 12" x 12" beige marble | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1032 : Business/Computer
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|---------------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | Acoustic Tile | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | Column | Drywall and joint compound, HWCDSB sample AGAT 19H455712 | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1033 : Math
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1034 : Math
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1035 : English/Social Science
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | S0009C | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1036 : LBS
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, 12" x 12" Beige marble | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Drywall and joint compound | | | A | Y | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1037 : Kitchen
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Textured (previously sampled) | | | C | Y | | 100 | | | | V0000 | Non-Asbestos | | None | |
| Floor | | Ceramic Tiles | | | A | Y | | | | | | | | | | |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Ceramic Tiles | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1038 : Cafeteria B and Storage
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1039 : Cafeteria A
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | S0009A | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1040 : Chef Office
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|----------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige Marble. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Piping | | Fibreglass | Straight | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1041 : Storage
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|----------------------------|------|----------|----|----|-----|--------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Drywall and joint compound | | | C | Y | | 100(7) | | | % | S0001C | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #1042 : Custodian **Floor:** 1
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Streak. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #1043 : Stairwell **Floor:** 1
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09 | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1044 : Stairwell
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1045 : Stairwell
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1046 : Stairwell
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1047 : Storage/ Kitchen
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Drywall and joint compound | | | C | Y | | 100(7) | | | % | S0001B | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Other | Sink | Mastic, Black, undercoating | | | A | N | | 1(7) | | | EA | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1048 : Balcony
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|-------------------|-----------|-------------------|------|----------|----|----|-----|------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | Deck | Steel | | | A | Y | | | | | | | | | | |
| Duct ¹ | | Textile | | | A | Y | | 1(7) | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

1 - Expansion joints - woven.

Client: Hamilton-Wentworth Catholic District Sch
Location: #1050 : Storage
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #1051 : Storage **Floor:** 1
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #1052 : Storage **Floor:** 1
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1053 : Corridor
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #1055 : Staff Mens Washroom
Survey Date: 2018-07-19

Site: Adult
Floor: 1

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|---------------|---|------------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | Acoustic Tile | Ceiling Tiles (lay-in), 2x4 Small and Irregular Pinhole (date stamped 08/23/09) | | | C | Y | | | | | | V0000 | Non-Asbestos | | None | |
| Floor | | Terrazzo | | | A | Y | | | | | | V0000 | Non-Asbestos | | None | |
| Piping | | Fibreglass | Insulation | | C | N | | | | | | V0000 | Non-Asbestos | | None | |
| Wall | | Masonry | | | A | Y | | | | | | V0000 | Non-Asbestos | | None | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2000 : Stairwell
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Black with White Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2001 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 25
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | Column | Drywall and joint compound, HWCDSD sample AGAT 19H455712 | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2002 : Hallway
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2003 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 24
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2004 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|---------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | S0009B | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 50(7) | | | % | S0010AB | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2005 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 22
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2006 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 21
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2007 : Stairwell **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Black with White Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2008 : Corridor **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Black with White Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | | | | | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Concrete (poured) | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2009 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 11
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Grey/White Dense Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | S0010C | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100 | | | % | S0003A | None Detected | N.D. | None | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2010 : Corridor
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Duct | | Fibreglass | | | C | N | | | | | | | | | | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Black with White Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | % | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2011 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 12
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Grey/White Dense Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100 | | | % | S0003C | None Detected | N.D. | None | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2012 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 13
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Grey/White Dense Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100 | | | % | S0003B | None Detected | N.D. | None | |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2013 : Men's Washroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Dark Grey with White Streak. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2014 : Custodian Room
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|----------------------------|------|----------|----|----|-----|--------|------|------|------|--------|---------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V0001 | Chrysotile | 0.5-5% | Confirmed Asbestos | NF |
| Floor | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Piping | | Fibreglass | | | C | N | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2015 : Caretaker Closet
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|--------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, 12"x 12". Dark Green with White Streak (previously sampled) | | | A | Y | | 100(7) | | | % | V9000 | Confirmed Asbestos | | Confirmed Asbestos | NF |
| Wall | | Concrete (poured) | | | A | Y | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2016 : Corridor **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Dark Grey with White Streak. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2017 : ESL Room **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: A **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Dark Grey with White Streak. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2018 : Copy Room
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|----------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2019 : Spare Room
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|----------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2020 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 14
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | | Drywall (no compound) | | | A | Y | | 100 | | | % | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2021 : Corridor
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall (no compound) | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2022 : Office
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | | Drywall (no compound) | | | A | Y | | 100 | | | % | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2023 : Office
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2024 : Office
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | | Drywall (no compound) | | | A | Y | | 100 | | | % | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2025 : Office
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|---------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Piping | | Parging Cement | Fitting | | C | N | | 2(7) | | | EA | V0004 | Chrysotile | 50-75% | Confirmed Asbestos | F |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2026 : Office
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2027 : Office **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31
Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2028 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 32 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|--|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Small and Irregular Pinhole. Date Stamped 08/23/09. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2029 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 33 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|--------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Other | Window | Caulking, white | | | A | Y | | | | | | V0009 | None Detected | N.D. | None | |
| Other | Window | Putty, grey | | | A | Y | | 100(7) | | | % | V0010 | Chrysotile | 5-10% | Confirmed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | 100 | | | % | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2030 : Stairwell
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: A
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | A | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2031 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 17
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2032 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 16 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2033 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 15 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2034 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 20 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | Column | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2035 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 19 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2036 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 18 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2037 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: 26 **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | Column | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2038 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 27
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | Column | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2039 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 28

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2040 : Corridor
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | | Drywall (no compound) | | | A | Y | | 100 | | | % | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2041 : Classroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 31
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |
| Wall | | Drywall (no compound) | | | A | Y | | 100 | | | % | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2042 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch **Site:** Adult
Location: #2043 : Classroom **Floor:** 2
Survey Date: 2018-07-19

Building Name: St Charles - Mountain Campus
Room #: **Area (sqft):** 0
Last Re-Assessment: 2023-07-31

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Beige with Brown Fleck | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Drywall and joint compound | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2044 : Eyewash Station
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #: 2
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|------|------|------|------|--------|---------------|--------|--------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Short Fissure Random Pinhole. Date Stamped 2010. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Ceiling | | Ceiling Tiles (lay-in), Ceiling Tile 2' x 4' Long Fissure Random Pinhole. | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Concrete (poured) | | | | | | | | | | | | | | |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2045 : Womens Washroom
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|-------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, Vinyl Floor Tile 12"x 12" Dark Grey with White Streak. | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Floor | | Mastic | | | D | N | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Client: Hamilton-Wentworth Catholic District Sch
Location: #2046 : Spare Room
Survey Date: 2018-07-19

Site: Adult
Floor: 2

Building Name: St Charles - Mountain Campus
Room #:
Last Re-Assessment: 2023-07-31

Area (sqft): 0

| ASBESTOS | | | | | | | | | | | | | | | | |
|----------|-----------|---|------|----------|----|----|-----|--------|------|------|------|--------|-------------------|--------|----------------------|---------|
| System | Component | Material | Item | Covering | A* | V* | AP* | Good | Fair | Poor | Unit | Sample | Asbestos Type | Amount | Hazard | Friable |
| Ceiling | | Ceiling Tiles (lay-in), 2' x 4' Long Fissure Random Pinhole (previously sampled) | | | C | Y | | 100 | | | % | V0000 | Non-Asbestos | | None | |
| Floor | | Vinyl Floor Tile and Mastic, 12" x 12" dark grey with white streaks | | | A | Y | | 100(7) | | | % | V9500 | Presumed Asbestos | | Presumed Asbestos | NF |
| Wall | | Masonry | | | A | Y | | | | | | | | | | |

Legend:



| Sample number | | Units | | Other | |
|---------------|--|-------|-------------|-------|------------------------------|
| S#### | Asbestos sample collected | SF | Square feet | A | Access |
| V#### | Material visually similar to numbered sample collected | LF | Linear feet | V | Visible |
| V0000 | Known non-asbestos material | EA | Each | AP | Air Plenum |
| V9000 | Visually identified as an asbestos material | % | Percentage | F | Friable material |
| V9500 | Material is presumed to be an asbestos material | | | NF | Non Friable material |
| | | | | PF | Potentially Friable material |

| Access | |
|--------|---|
| A | Accessible to all building occupants |
| B | Accessible to maintenance and operations staff without a ladder |
| C | Accessible to maintenance and operations staff with a ladder. Also rarely entered, locked areas |
| D | Not normally accessible |

| Condition | |
|-----------|---|
| Good | No visible damage or deterioration |
| Fair | Minor, repairable damage, cracking, delamination or deterioration |
| Poor | Irreparable damage or deterioration with exposed and missing material |

| Visible | |
|---------|---|
| Y | The material is visible when standing on the floor of the room, without the removal or opening of other building components (e.g. ceiling tiles or access panels). |
| N | The material is not visible to view when standing on the floor of the room and requires the removal of a building component (e.g. ceilings tiles or access panels) to view and access. Includes rarely entered crawlspaces, attic spaces, etc. Observations will be limited to the extent visible from the access points. |

| Air Plenum | |
|------------|---|
| Yes or No | The material is in a return air plenum or in a direct airstream or there is evidence of air erosion (e.g. duct for heating or cooling blowing directly on or across an ACM). This field is only completed where Air Plenum consideration is required by regulation. |

| Colour Coding | |
|--|---|
|  | The material is known to contain regulated concentrations of asbestos; either by analytical results or visible identification (use of the V9000 code). |
|  | The material is presumed to contain asbestos; based on visual appearances; typically a material known to historically contain asbestos; however, not sampled due to limited access or the destructive nature of the sampling. |

| Action | | | | | |
|--------|--|-----|--|-----|-------------|
| (1) | Clean up of ACM Debris | (2) | Precautions for Access Which may Disturb ACM Debris | (3) | ACM removal |
| (4) | Precautions for Work Which may Disturb ACM in Poor Condition | (5) | Proactive ACM removal (Minimum repair required for fair condition) | (6) | ACM repair |
| (7) | Management program and surveillance | | | | |